

AutoStore®

Intralogistics with
limitless dynamics





Red Line robot

Grid

Hoisting belts

Gripper plate

Bin

Multi-temperature solution

Combining frozen, chilled, and ambient storage environments

High-throughput solution


Capabilities of 20,000+ picks per hour

Maximally condensed storage



Warehousing goes four-dimensional

Take control of space and time



Time pressure in order picking? No more space for incoming goods? Endless routes from shelf to shelf? Then you need an ASRS solution that is perfectly tailored to your individual needs in terms of time and space.

AutoStore and Swisslog's knowhow opens up a new dimension in small parts logistics. Swisslog is a leading global integrator of the AutoStore system.

With AutoStore and Swisslog, you create the basis for keeping the typical challenges of small parts warehousing under control sustainably and efficiently.

Advantages of AutoStore


- Handle unexpected order peaks flexibly and cost-effectively with additional robots
- Master growing assortment ranges easily with additional bins
- Create more capacity and expand the system on the fly
- Link AutoStore with existing IT systems and subsystems

- 1 Red Line robot
- 2 Red Line charging station
- 3 Sensor cleaning station
- 4 Service platform
- 5 Lifting belt cleaning station
- 6 ConveyorPort
- 7 ItemPiQ robot item picking
- 8 Conveyor interface
- 9 CarouselPort Pick-by-light high performance picking

Suitable for all kinds of products and industries:



Pharma



Food > -26 °C



Spare parts




E-Commerce



Electronics



Fashion



Building products






Cosmetics



Why AutoStore

Empowered by Swisslog



Compact & versatile

AutoStore is suitable for the storage of small-volume goods of various types. The unit size is limited only by the volume of the bins.

- Maximum utilization of the available space
- Only one system for all industries including chilled and deep freeze
- Can be used individually for classic warehousing, e-commerce fulfillment, production supply, logistics service providers, and much more

Fast & efficient

AutoStore decreases the effort of manual picking to a minimum, if it is even required at all, and provides continuous operation 24/7.

- Accelerated order processing through automated provision of all items
- A single grid can support 20,000+ bin presentations per hour; multiple grids can work together to support even higher throughputs.
- High process reliability thanks to central control system
- Easy integration into existing IT systems

Flexible & scalable

AutoStore can be easily integrated into existing buildings. Capacity can be increased with additional robots and/or bins, and the basic design can also be expanded.

- Future-proof design due to modular construction
- Redundancy (picking stations can be operated by all robots for extremely high system availability)
- Minimal maintenance required
- Simple integration with conveyor systems and other subsystems

The grid

Robust backbone


A self-supporting structure of aluminum rails, the grid is divided into rectangular elements to form the backbone of each AutoStore system.

Goods are stored in bins inside the grid. On top of the grid, robots take over the storage and retrieval of the bins, transferring them to workstations where goods can be removed.

If required, they can also be used in sensitive environments or designed to be ESD-compliant.




Classic system



System on steel platform


Workstations underneath



Connected system over several levels

Facts

Capacity per system:	5,000 to 300,000 storage boxes
Capacity per field:	up to 26 storage boxes vertically
Maximum height of bin storage:	6.0 m
Minimum distance from ceiling:	1.8 m
Length and width of structure:	almost infinitely scalable



*Deep freeze: special setup with air circulation & humidifier

The robots

Standardized, fast and efficient

Robot R5 or R5+, standard or high performance: the type and number of robots used on the grid essentially determines the throughput of the AutoStore system.

By using additional robots and/or modifying the control software, the performance of the overall system can be easily increased as required.

R5 Pro and R5+ Pro robots offer a high performance upgrade to the AutoStore system. With enhanced bin handling and smarter energy use, they help increase throughput while optimizing grid space. The R5+ Pro significantly reduces the number of required chargers, lowering system investment and installation costs, and freeing up space to store more SKUs.

AutoStore R5 & R5+

- Storage and retrieval: average 25/h
- Speed: max. 3.1 m/s
- Storage container pick-up: next to robot body



AutoStore R5 Pro & R5+ Pro

- Storage & retrieval: ~14% higher throughput per robot
- Speed: max. 3.1 m/s
- Bin handling:
R5 Pro: 220- & 330-mm bins
R5+ Pro: up to 425-mm bins




Storage containers

For larger small parts

AutoStore allows the definition of small parts to be handled quite flexibly. Whether a storage bin is filled with just one item or thousands of small parts depends solely on individual requirements. Three bin types with a uniform footprint are available in different heights.



For easier handling, the inside of storage containers can be further adapted with longitudinal and transverse dividers.



220 mm storage bin

Compatibility:	All robots
Stacking height:	max. 26 pcs.
Volume:	49.08 liters
Load capacity:	max. 30 kg

330 mm storage bin

Compatibility:	All robots
Stacking height:	max. 18 pcs.
Volume:	75.81 liters
Load capacity:	max. 30 kg

425 mm storage bin

Compatibility:	R5+ Pro
Stacking height:	max. 14 pcs.
Volume:	98.17 liters
Load capacity:	max. 30 kg

Workstations

Convenient handling areas

Store and retrieve goods, pick orders and do away with walking long distances: AutoStore workstations create maximum efficiency and make every movement easier, creating a highly ergonomic workplace for operators.



CarouselPort is the most popular port with very high storage and picking performance. Three rotating arms ensure continuous provision of storage containers.



ConveyorPort presents storage containers one after another on a conveyor belt. This is simple, safe and adapted to the speed of each individual operator.




SwingPort can be placed anywhere below the grid and has a direct connection to a storage bin lift. The two arms rotate.



With **RelayPort**, robots can place and pick up several storage containers in parallel, improving the sequencing of orders.




PickUpPort is a publicly accessible AutoStore port where customers can pick up orders directly and contactlessly in the store. It is an innovative solution for omnichannel retail sales.



FusionPort is designed to meet users' needs, with sloping bin openings and ergonomic positioning of the user interface.



FusionPort Staging has two exit bin openings in the center and two destination bin openings on the left and right. Finished jobs go back into the grid without taking up additional floor space.



ClusterPort is an in-house development by Swisslog for highly efficient storage of products. Containers with the required subdividers are provided automatically by the storage software.



VersaPort is a modular workstation designed to enhance the functionality of the ConveyorPort. It can be deployed as a single unit or configured in multiple ports for more complex operations.

Picking & packing

Pick-by-light, conveyor technology & more



- 1 CarouselPort
- 2 Boxes on a four-position pick-to-light marking system
- 3 Bin presentation
- 4 Pick-by-light: laser beam marks removal compartment
- 5 Pick display: guides picker through picking process
- 6 Forwarding of orders ready for shipment

AutoStore workstations can be linked directly to upstream and downstream intralogistics systems to ensure that orders reach recipients even faster.

Swisslog-developed conveyor systems also ensure automatic delivery of target containers and removal of source containers, so that picking workstations do not have to be positioned directly on the AutoStore system.

Maximum automation of shipping preparation saves space and distances, while at the same time significantly increasing throughput compared to purely manual packaging processes.

To facilitate packaging operations, Swisslog creates a smooth transition to third-party sub-systems and light goods conveyors, such as:

- Box formers
- Box sealers
- Box lidding machines
- Labelers
- Weighing scales
- Palletizers

ItemPiQ by Swisslog

Robotic piece picking

ItemPiQ is Swisslog's self-learning robotic picking solution, designed to improve warehouse order fulfillment. Using advanced AI and precision robotics, it delivers fast, accurate, and reliable performance.

It integrates easily into various warehouse setups and adapts to different product types and sizes. ItemPiQ supports picking, placing, and sortation tasks, and fits seamlessly into Swisslog's Goods-to-Robot (GtR) solutions.

The advantages are:

- Fast order fulfillment: ItemPiQ sets the bar high by operating 24/7 at speeds of up to 1,000 items per hour.
- Adaptability: ItemPiQ is leveraging advanced self-learning AI technology and precise robotics to handle a wide range of products.
- High pick & place reliability: ItemPiQ excels in delivering consistent, error-free picking while ensuring excellent error handling processes.
- Seamless integration: ItemPiQ is seamlessly integrated into the SynQ WMS and has a standard interface to any WMS system.
- Expertise & global support by Swisslog



Facts

Lifting capacity:	max. 3 kg per individual part/container
Capacity:	up to 1,000 items/h (technical possible performance)
Product types:	variable (multifunction gripper)
Item deminsion:	surface max. 300 x 300 x 300 mm

Software: SynQ by Swisslog

Digital hub and spoke

SynQ links AutoStore control functions with customer specific components such as existing ERP, WMS and MFCS installations or automated material flow control system solutions (conveyors, pallet systems, AGVs, etc.).

Quick and easy to set up, SynQ synchronizes and optimizes all warehouse processes and creates absolute transparency at all levels and in real time.

SynQ from Swisslog:

- A field-proven platform with well over 400 customer installations
- Compatible with all common third-party ERP systems
- Cloud-based as well as on-premise deployable
- Modular design with unlimited extendibility
- Capabilities that maximize AutoStore throughput and operating flexibility

SynQ[®]

ROFU
Spielwaren und mehr!

DB SCHENKER

STIHL

Yusen Logistics

RADWELL
INTERNATIONAL INC.

biopartner

Sportamore

LIINFOX


arvato
BERTELSMANN



Combining AutoStore with SynQ or SAP EWM achieves the highest performance:


- Function for consolidating similar-sized products into multiple bins. This increases the optimal use of storage capacity (bins become free).
- Batch picking hit rate optimized by grouping orders and order positions. Orders are processed in parallel faster by means of an algorithm and unnecessary transports of Autostore bins are minimized.

Automate logistics processes with SynQ



System integration

SynQ integrates seamlessly into intralogistics processes and communicates with all existing WMS installations




Warehouse management

SynQ is linked to AutoStore software and has real-time access to inventory data for all stored items.



Order scheduling

Incoming orders can be pre-scheduled on time or individually prioritized to AutoStore.




Picking

After data transfer, AutoStore automatically assembles the ordered items and transfers the goods to a workstation for shipment preparation.



Shipping preparation

Swisslog conveyor technologies ensure the automated provision of source and destination bins as well as a smooth transition to downstream packaging plants.



SynQ Cockpit

Based on recorded process data, all processes can be reconstructed and analyzed in detail to identify possible weak points and further improve overall performance.

AutoStore with SAP EWM

Bringing warehouse management up to full speed




By linking AutoStore with SAP EWM, Swisslog paves the way for a holistic material flow control with a wide range of functions.

SAP EWM can be easily and seamlessly integrated into existing SAP structures – as a decentralized system or embedded in SAP S/4 HANA environments.

Swisslog's services as an SAP Silver Partner include, among others:

- Integration of data generated by AutoStore into the functionality of SAP EWM
- Migration SAP WM to SAP EWM
- EWM implementation fully integrated into warehouse processes with or without automation technology
- Creation of EWM templates for customers with multiple locations to standardize logistics processes across the company
- 24/7 support (Level 2 & 3) for all SAP EWM managed processes (in-house and third-party systems)



- Pick-to-light system for parallel picking at workstations increases picking performance many times over
- Highly intuitive user interfaces enable fast onboarding of new employees
- Clear guidance in the user interface leads to virtually error-free picking



Service & support

At your service always and everywhere




Available immediately 24/7, worldwide and directly represented at more than 25 international service locations, our comprehensive support ensures that AutoStore systems serviced by Swisslog are on average available 99.6 % of the time.

Swisslog's support services include, among others:

- Customer-specific training on the use of hardware and software
- RemoteAssistance or SelfAssistance using augmented reality applications
- Support for connected software installations (e.g. SynQ and SAP EWM)



Last but not least, the technologies developed by Swisslog for gentle sensor and gripper belt cleaning ensure a long product service life and low maintenance costs.



Robot Sensor Cleaning Station

Customer success

Examples



40,600 bins, 22 robots, 11 ports: Using AutoStore, Yusen Logistics in Singapore was able to increase warehouse capacity from 2,000 to 3,500 m³ with the same floor space and increase order throughput by 200 %.




arvato

With a system of multi-order workstations and mobile pick-to-light storage racks, Swisslog has enabled healthcare provider Arvato to process up to 25,000 orders a day.

VARNER

In Scandinavian textile company Varner's new distribution center, AutoStore forms the heart of a state-of-the-art total logistics solution for every conceivable requirement of omni-channel retailing.




true

At the exclusive True Branding Shop in Bangkok, AutoStore ensures a wide selection of the leading company's products are available for immediate purchase in its retail outlet.




La Réserve des Saveurs, a family-run business specializing in culinary trades and food distribution in France, has implemented a revolutionary project for combined dry, cold, and frozen food logistics with AutoStore.



To flexibly adapt warehouse capacity in line with growth, Italian specialist retailer of lighting, electrical and electronic goods, Fabbri Imola has comprehensively automated its intralogistics with AutoStore.




With connected light goods conveyor technology as well as automated picking and packing, AutoStore ensures maximum efficiency and flexibility in the logistics center of Scandinavia's largest online sports goods store.



Significantly improved space utilization and halved picking times have been achieved by UK retailer ASDA using AutoStore in an integrated distribution center.

World's leading AutoStore integrator

The Swisslog advantage



Why Swisslog


Proven benefits



With more than 400 projects worldwide, Swisslog is a leading AutoStore integrator. Benefit from connections to subsystems such as conveyors or pallet handling.



In addition to hardware, Swisslog also offers efficient software solutions for optimal warehouse management.



Intelligent robotics from Swisslog accelerates workflow and opens up new dimensions in intralogistics.



With the high energy efficiency and cost-effectiveness of AutoStore, Swisslog creates sustainable material flow systems.